

International Workshop on  
“New Aspects of the Hadron and Astro/Nuclear Physics”  
National University of Uzbekistan, Tashkent, November 5-10, 2018


# Status of LAMPS at RAON for Nuclear Symmetry Energy




Byungsik Hong  
(Korea University)



□ **RAON: Rare isotope Accelerator**  
complex for **ON-line** experiments






- Basic design finished in Dec. 2015
- Construction company selected in Sept. 2016
- Ground breaking in Feb. 2017









- Project period: Dec. 2011 ~ Dec. 2021
- Scope: Accelerator Facility, Buildings & Utilities
- Budget: Total ~U\$ 1.43B
  - Accelerator and Expt. Facility: ~U\$ 0.46B
  - Building & Utility: ~U\$ 0.97B (including the land cost)
- Host: Ministry of Science and ICT (MSIT)



	Driver Linac				Post Acc.	Cyclotron
Particle	H <sup>+</sup>	O <sup>+8</sup>	Xe <sup>+54</sup>	U <sup>+79</sup>	RI beam	proton
Energy (MeV/u)	600	320	251	200	18.5	70
Current (pμA)	660	78	11	8.3	-	1000
Power (kW)	> 400	400	400	400	-	70











RAON aims to provide an access to unexplored regions of nuclear chart.

J. W. Shin et al., NIMB349, 221 (2015)

- Yield ratio:  $^{132}\text{Sn} + ^9\text{Be} / ^{238}\text{U} + ^9\text{Be}$
- ISOL+IF is beneficial, for example, for the n-rich isotopes for  $45 \leq Z \leq 50$





Design & Fabrication

Installation & Test (Munji Campus)

Transfer to main site

Commissioning

Operation



2011~2014

~2019.06

~2019.12



2020

2021



## 28GHz ECR test results

- Successful extraction
  - $O^{7+}$  of 30euA,  $Ar^{11+}$  of ~70euA
- After cry-cooler maintenance, cooling capacity margin improved



Purchasing process

Manufacturing

Installation & Commissioning

Operation

2018

~2019

~2020.5




2020.6~

- A secondary ion source
- 14.5 GHz ECRIS and 28 GHz ECRIS will supply a stable isotope beam to SCL3 alternately.
- 14.5 GHz ECRIS will be a main ion source when 28 GHz ECRIS moves to SCL1

Conceptual design	Prototype	<b>Test &amp; Upgrade</b>	Installation	Commissioning	Operation
2011~2012	~2015	~2018	2019	2020	2021



## Installation & Test of injector @ SCL demo

- Completion of manufacturing and tuning of RFQ (Quad. Field  $< \pm 2\%$ , Dipole Field  $< \pm 5\%$ )
- Installation of injector and test for beam acceleration performance of RFQ ( $> 500$  keV/u)



RFQ at SCL DEMO

### RFQ tuning result



**SCL3**  
(QWR/HWR)

Conceptual design	Prototype	Test and Manufacturing	Installation	Commissioning	Operation
2011~2012	~2016	~2018	2019	2020	2021

**SCL2**  
(SSR1/SSR2)


Conceptual design	Prototype	Test and Manufacturing	Installation & Commissioning	Operation
2011~2012	~2018	~2019	~2021	2022




QWR



HWR




SSR2



## Superconducting cavity test

- SRF test facility @ KAIST Munji Campus
- Manufacturing and Performance test for QWR x 4, HWR x 6, SSR1 x 1 is under way ('18)



Result of HWR cavity performance test





Cavity test pit, Cryostat, Control room

## Cryomodule test

- Cryomodule test facility set up
- Completion of performance tests for QWR module and HWR module A (two cavities)

### QWR module





Total thermal load at various Eacc

$E_{acc}$ (MV/m)	6.1	6.4	7
$Q$ (W)	9.9	13	23.7


Target total thermal load @ 6 MV/m : **25 W**

### HWR module A




$Q$ (Static)	$Q$ (Dynamic)	$Q$ (Total)
6.6 W	1.4 W (cavity#1)	12.8 W
	4.8 W (cavity#2)	


Target total thermal load @ 2.92 MV : **14.1 W**



□ Prototype of SSR2 cavity designed by the RISP accelerator team is in procurement process.



□ Two-track strategy to minimize the risk in the development









Cyclotron

Contract with "Best Cyclotron"  
(Canada) in April 8, 2017

Procurement	Manufacturing & delivery	Install. & commi.	beam to ISOL
2016~2017.4	2017.4~2019.3	2019.4~2020.3	2020~

ISOL

Conceptual design	Prototype	Manufacturing	Installation	Commissioning	Operation
2011~2012	~2017	~2019.3	~2020.7	2021.6	2021

System	Specification	Current Status
Target ion source	<ul style="list-style-type: none"> <li>• UCx fission target (10 kW)</li> <li>• SIS, RILIS, FEBIAD</li> </ul>	<ul style="list-style-type: none"> <li>• Manufacturing (partly)</li> </ul> 
Beamline, Remote handling, Hot cell system (incl. A/q separator)	<ul style="list-style-type: none"> <li>• <math>R_{A/q}</math>: ~200 (for EBIS)</li> <li>• E+B Combination</li> </ul>	<ul style="list-style-type: none"> <li>• Purchasing process</li> </ul> 
RFQ cooler & buncher	<ul style="list-style-type: none"> <li>• Cooling time : &lt; 100 ms</li> <li>• Transmission <math>\epsilon &gt; 50\%</math> (Sn)</li> <li>• Output emittance: &lt; 3</li> <li>• Capacity: &lt; <math>10^8</math> ions/bunch</li> </ul>	<ul style="list-style-type: none"> <li>• Under design</li> </ul> 
EBIS charge breeder	<ul style="list-style-type: none"> <li>• E/A : 10 keV/u</li> <li>• A/q : 10 keV/u</li> <li>• <math>\epsilon = 15\%</math> (<math>^{133}\text{Cs}^{27+}</math>)</li> <li>• Breeding time: 50~100 ms</li> <li>• Capacity: &lt; <math>10^8</math>/bunch</li> </ul>	<ul style="list-style-type: none"> <li>• Start integration of                             <ul style="list-style-type: none"> <li>– e-gun/collector</li> <li>– SC solenoid</li> <li>– Drift tube</li> </ul> </li> <li>• Breeding test ('18.12~)</li> </ul> 

Conceptual design	<b>Prototype &amp; Test</b>	Manufacturing	Installation	Commissioning	Operation
2011~2012	<b>~2018</b>	~2020.11	~2021.7	2021.12	2022~


### Target/dump: Staged 80 kW → 400 kW

- **Target:** multi rotating graphite disks, benchmarking of FRIB design
- **beam dump:** two water-filled rotating disk
- finalizing manufacturing design, start manufacture from 2019

### Magnet

- 8 dipole magnets and 15 quadrupole magnet triplets
- HTS, LTS: finish of prototype test
- Production start from end of this year

**Max. beam power : 400 kW**  
**<sup>238</sup>U beam energy : 200 - 400 MeV/u**




**Main Parameters**

Max. Bρ	~ 9.6 T.m
Δp/p	<±3%
Angular acceptance	±40 mrad (H) ±50 mrad (V)

**IF Magnets**

HTS Dipole (x1)	LTS Dipole (x7)
HTS Quad. (x6)	LTS Quad. Triplet (x13)
HTS Hexapole(x1) NC Hexapole (x1)	LTS Hexapole (x13)

- HTS (LTS): High (Low) Temperature Superconducting
- NC: Normal Conducting



## (Korea Broad acceptance Recoil spectrometer and Apparatus)

Conceptual design

Prototype & Test

**Manufacturing**

Installation & Commissioning

Operation

2011~2012


~2017.9

~2019.4

~2020.12


2021.1~

- The first part of stage1 (stage1 part1) was contracted with foreign & domestic companies in April 2018. (Presently, parts are being produced.)
- The design of second part of stage1 (stage1 part2) was finally done among the various options in June, 2018 after consultation with potential domestic users.
- The stage1 will be installed in the Low Energy Expt. room (E1) by the end of June 2020.
- The commissioning of Stage1 will start in the beginning of 2021 with stable ion beams.




### PPAC

- Two 10x10 cm<sup>2</sup>, two 20x20 cm<sup>2</sup>, and one 40x20 cm<sup>2</sup> active area PPACs were built.
- Four 10x10 cm<sup>2</sup> and one 40x20 cm<sup>2</sup> PPACs will be built in addition.



### SSD

- Two 16 Channel detectors with 5x5 cm<sup>2</sup> active area and 50 μm thickness
- Energy resolution ~0.7% and S/N ~272 for 5.5 MeV α in vacuum



### Plastic scintillator detector

- Two detectors read out both ends with 10x10 cm<sup>2</sup> active area and 100 μm thickness
- Time resolution < 42 ps for 5.5 MeV α in vacuum

## (Large Acceptance Multi-Purpose Spectrometer)

Conceptual design

**Prototype & Test**

Manufacturing

Installation

Commissioning

Operation

2011~2012


~2018.12

~2020.12

~2021.7


2021.12

2022~



- Beam energy: 250 MeV/u for  $^{132}\text{Sn}$
- Solenoid Spectrometer
  - Maximum 1 T solenoid magnet
  - TPC ( $\sim 3\pi$  sr coverage for tracking)
  - Barrel scintillation counter (trigger & ToF)
- Forward neutron wall (neutron energy spectrum)

### Solenoid Magnet




Superconducting magnet

Coil radius: 0.8 m

Specifications

- Nominal operation B-field: 0.5 T
- Maximum B-field: 1 T,  $\Delta B/B < \pm 1\%$  in the TPC region

### Time Projection Chamber (TPC)




Test completed with prototype TPC

Fulfill the requirement

Specifications

- GET electronics read out from one side
- Gas mixture: P-20

### Forward Neutron Detector Array



Completed extensive R&D

Detector construction is in progress  
Construction will be completed by the  
end of 2018

# HPMMS: MR-TOF

## (High Precision Mass Measurement System)

Conceptual design

**Manufacturing & Test**

Installation

Commissioning

Operation

2011~2012


~2020.1

~2020.10



~2021.12


2022~

- R&D performed by the WNSC MRTOF group (Leader: Prof. Wada).
- Additional beamline to the MRTOF-MS system was constructed in 2017.
- Differential pumping system, gas cell (or catcher), trap system, and MRTOF analyzer were assembled, waiting for the offline ion-source test.
- Test of the differential pumping system with the gas cell filled with 1 mbar helium gas was performed at  $3.4 \times 10^{-4}$  Pa upstream side (acceptable).
- Optimizing the beam transmission through the  $\phi=2$  mm gas cell hole was performed: 72% efficiency achieved (It will be improved by additional beam steerer.)



A picture of MRTOF-MS system and other parts at RISP-KEK/WNSC






# LAMPS: Large-Acceptance MultiPurpose Spectrometer








(RAON)





(RAON)



# Time Projection Chamber




Simulation of one central  
Au+Au event at 250 AMeV  
(IQMD)



# Prototype TPC: Design

## Prototype TPC with half dimensions





[Readout Pads]

Tested pads with the two different dimensions

$3 \times 10 \text{ mm}^2$ : 357 Ch./Oct.

$4 \times 15 \text{ mm}^2$ : 175 Ch./Oct.

Multi-layer PCB board





[GEM Foil]

Trapezoidal shape

Thickness:  $75 \mu\text{m}$

Area:  $166 \times 118 \text{ mm}^2$

Triple layers for each plane



[Field Cage]


$35 \mu\text{m}$  thick and 2 mm wide Cu strips

$500 \mu\text{m}$  gap between adjacent strips

Mirror strips on the back

1 M $\Omega$  resistors with 0.1% var.



TPC body: G10 + Aramid honeycomb





Inner Field Cage installed

Outer Field Cage installed

Prototype TPC assembled





Prototype TPC: back




- ELPH: Research Center for Electron Photon Science at Tohoku University, Japan
- Dates: November 2016
- Beams:  $e^+$  beams at 500 MeV
- Gas: Ar(90%)+CH<sub>4</sub>(10%) (P10)  
Ar(90%)+CO<sub>2</sub>(10%) (ArCO<sub>2</sub>)
- Purpose: To study the detailed characteristics, such as  $v_{drift}$ , diffusion and  $\sigma_x$ , of LAMPS TPC








P10, 155 V/cm





Preliminary



- $v_{drift} \lesssim 5.3 \text{ cm}/\mu\text{s}$  for P10:  
 Maximum distance:  $512 \text{ timing bins} \times 0.04 \mu\text{s}/\text{bin} \times 5 \text{ cm}/\mu\text{s} \cong 100 \text{ cm}$
- Tested P20 with cosmic muons:  $v_{drift} > 6 \text{ cm}/\mu\text{s}$  that will be suitable for LAMPS TPC if read out from only one endcap side.

Preliminary



$$\sigma_{\text{track}}^2 = D^2 z + \sigma_0^2$$




where

$z$ : drift length




$\sigma_{\text{track}}$ : width of hit distributions  
w.r.t. the fitted track

$D$ : diffusion coefficient

$\sigma_0$ : coefficient depending on the amplification system






# Neutron Detector Array



- E479 approved in B-PAC in March 2016
- Date: May 2016
- Beam specifications
  - Protons on Li production target ( $p+{}^7\text{Li} \rightarrow n + {}^7\text{Be}$ )
  - Neutron energies: 65 and 392 MeV in N0 beamline
  - 10 nA flux  $\times$  1/9 chopping
  - Background neutron above 3MeV is less than 1% [NIMA629, 43 (2011)]



Chopping signals





- Distance from target to the detector: 15 m
- Gap between stations: 60 cm
- Dim. of each S1 detector:  $10 \times 10 \times 100 \text{ cm}^3$
- Dim. of each S2 detector:  $10 \times 10 \times 200 \text{ cm}^3$
- Beam size at S1:  $25 \times 30 \text{ cm}^2$

Preliminary



- Time resolution:

$$\Delta t = \sqrt{(\Delta\tau)^2 + (\Delta x/v)^2} = 0.66 \text{ ns}$$

where

$$\Delta\tau = \text{FWHM of } \gamma \text{ peak} = 0.60 \text{ ns}$$

$$\Delta x = \text{effective thickness of the detector} \\ = (\text{Total thinness of Li target, veto,} \\ \text{and neutron detector})/2 = 6.0 \text{ cm}$$

$$v = \text{neutron velocity} = 21.3 \text{ cm/ns}$$

- Neutron energy resolution:

$$\frac{\Delta E}{E} = \gamma(\gamma + 1) \frac{\Delta t}{t} = 3.2\%$$


where

$$\text{Lorentz } \gamma = 1 + E/mc^2 = 1.42$$

$$t = 70.4 \text{ ns}$$

- Energy resolution (FWHM/E) = 3.3 %

Preliminary




- Hit position difference between  $D1$  and  $D2$  for neutrons:

$$\Delta x_{S1} \equiv x_{D1} - x_{D2}$$

for 10 MeV threshold and  $\delta t < 3$  ns

- Relative position resolution for neutrons for one bar:

$$\sigma_n = \frac{\sigma(\Delta x_{S1})}{\sqrt{2}} = 3.1 \text{ cm}$$



- Position difference between the projected hit position and the hit position for  $D3$  for cosmic muons:


$$\Delta x_{S2} \equiv x_{D3,proj} - x_{D3,hit}$$

- Relative position resolution for cosmic muons for one bar:


$$\sigma_\mu = \frac{\sigma(\Delta x_{S2})}{1.87} = 3.1 \text{ cm}$$




Curing UV glue



Fixing light guide with vice




Closeup view of the interface between scintillator & lightguide




- ↙ Clamps for installing PMTs
- ↓ Frames in the assembly site at the Sejong Campus of Korea Univ. close to RAON complex




Cosmic-ray hit dist.



Attenuation




Timing resolution




Parameters	Performance
MIP peak position variance	~10% (based on 9-10k events)
Attenuation length	$339 \pm 2$ cm (50% for 2m)
Speed of light in detector	$156 \pm 2$ mm/ns

Position resolution



*So far 5 domestic  
Universities and IBS*



- We invite more collaborators, especially, from foreign countries.
- Contact me ([bhong@korea.ac.kr](mailto:bhong@korea.ac.kr)) if you're interested in the project.

- The Rare Isotope Science Project (RISP) at IBS is the first large-scale nuclear physics project in Korea.
- The civil engineering, accelerator development, and detector construction for RAON have been aggressively progressed.
- LAMPS is a dedicated spectrometer for nuclear symmetry energy at RAON.
- Various components for LAMPS, including TPC, neutron detector array, magnet, are making a very good progress.
- Expect to finish the detector construction in about 2-3 years for early nuclear physics experiment.